



Transmission Grid Expansion – Challenge, Actions & Opportunities

Consulting Engineers South Africa (CESA)

Date: 10 August 2022

Background



- Background
- What is the CHALLENGE?
- Major projects in the TDP
- Recent and planned infrastructure additions
- Recent and planned capex
- Current grid capacity
- Status of resource adequacy
- What ACTIONS has Transmission taken?

Background



Current situation

The IRP 2019 gazetted in Nov 2019, proposes **9.8 GW** of new generation capacity to be connected by **2025** followed by **17 GW** of capacity (of which 11 GW is for RE) to be connected between **2026 to 2030**. Failure to deliver will lead to a security of electricity supply risk for the country

Current network reliability constraints (i.e. N-1), meeting organic demand growth and closing the refurbishment backlog also require significant new network infrastructure

This will require an **acceleration of investments** in Transmission infrastructure by development of new corridors and substations, and strengthening at existing substations over the period 2022 – 2031 to address both the IRP2019 as well as the network strengthening requirements across the country for **security of supply**




Problem statement

The grid strengthening required to accommodate this aggressive renewable integration and other needs requires significant investments

Timeline to implement Transmission lines can be 8 – 10 years, due to servitude challenges

The **resource capacity** in the country across the delivery value chain is limited

Capital requirements to achieve the TDP are substantial




What is the CHALLENGE?



We are facing coal decommissioning -


9,5GW by 2030 and continues beyond




IRP process has done its work

				IRP 2019				A
	Delta	Total	Gas	Wind	PV	Storage	Coal	
	0	1847		300	114		1433	2020
	0	2551		818	300		1433	2021
1	3113	4224		1600	1400	513	711	2022
9.7G	2850	3350		1600	1000		750	2023
9.76	2100	2600	1000	1600				2024
l	1730	2600		1600	1000			2025
	-3150	1600		1600				2026
	550	4350	2000	1600			750	2027
17G	-1800	2600		1600	1000			2028
176	-1275	4175		1600	1000	1575		2029
	0	2600		1600	1000			2030
	4118	32497	3000	15518	6814	2088	5077	Totals:
	1							

	1.87 GW					11.66 GW												
2022	711				400				2022	711	-844			513	400 1000	1600		
2023	500								2023	750					1000	1600		
2024	500								2024			1860				1600		1000
2025					670	200			2025						1000	1600		






Renewables brought forward from 2018 IRP to 2019 IRP by 9,8GW


NB: Excludes acceleration of BW6 from 2600MW to 5200MW

What is the CHALLENGE?



Northern Cape with most efficient solar resource taking into account DFFE and CSIR restriction areas has no connection capacity after BW5 / RMIPPP






Transmission network infrastructure augmentation in areas with Renewable Energy resources is critical for the country to maximise on the lowest cost energy

What is the CHALLENGE?






Identification / siting and securing suitable land or rights is a lengthy process particularly for linear developments and influences the timing and success of a projects

Major projects in the TDP FY22-FY31





Planned Infrastructure Additions




Transmission Assets Nationally	New Assets expected 2022 - 2026	New Assets expected 2027 - 2031	Total New Assets							
Power lines (km)										
765 kV	76	2668	2744							
400 kV	2348	3015	5363							
275 kV	174	125	299							
Total length (km)	2598	5808	8406							
Transformers										
Number of units	35	84	119							
Total capacity (MVA)	13445	45 345	58790							
Capacitors										
Number of units	7	15	22							
Total capacity (MVar)	376	836	1212							
Reactors										
Number of units	8	21	29							
Total capacity (MVar)	760	4 500	5260							



Recent Infrastructure Additions







Recent and Planned Infrastructure Additions



~ 8406 km of line:




~ 119 transformers ~ 58 GVA:



- F22-26 cf F17-21: **73**% increase in line km, **94**% increase in transformers
- F27-31: **124%** increase in line km, **140%** increase in transformers

Recent and Planned Capex






Current Grid Capacity – North & South



- 1. Eskom grid unlocking **Mpumalanga initiative** to encourage use of grid capacity
- 2. Enable additional capacity for renewables in the Western Cape by dispatching management of OCGT.
- 3. Access to grid capacity though local grid expansions identified.
- 4. Initiated major corridor strengthening.

32 GW of Existing Tx Grid Supply Area Capacity

Max ~19 GW likely for Utility Scale Renewable Grid Capacity



Current Grid Capacity – North & South



Background

New projects required to accelerate connection of IPPs in the grid. These projects are required by **2027**.

Summary of North

12 projects requiring 27 transformers. R8,1Bn investment, of which R3Bn is in the TDP.


Summary of South

10 projects requiring 18 transformers. R5,8Bn investment, of which R3,9Bn is in the TDP.

Summary

Projects in the TDP require rephasing. There are 18 additional projects, requiring R7Bn and 36 transformers

North (Inland) - 5.7GW (now) to 12,3GW



South (Inland) - 0.7GW (now) to 4,7GW



Status of resource adequacy



ITEM	CURRENT CAPACITY	SHORTFALL	PLANS
Large Power Transformers	~ 4? per year	~ 8 per year immediate	Local hesitant to expand; accredited 14 overseas factories; 7 more planned
Steel	30k tonn/year	23k tonn/yr from FY29; mills adequate; require a 2nd fabricator	Require a second supplier; industry development. May require permission to import
Insulators	15k per year	Small risk from FY30	Can be delivered if certainty around volumes is guaranteed
Conductor	20k km per year	10k km per year from FY30	OEM recently presented better plans
Line Construction	400km per year	400 - 800km per year	Training of existing; incubation of new; international players

What ACTIONS has Transmission taken?




- 1. TDP SteerCo, initially chaired by COO and now by GE; Dec '20
- 9 Streams looking at Planning, Proj Dev't, Lands & Rights, Procurement, Execution, Finance, Stakeholder Management, SD&L
- 3. Some key items being driven
 - 3.1 Engagement of DPWI/DPE at ministerial level regarding **release of govt land** and **expropriation** (Wave 1 of projects)
 - 3.2 Eskom achieving **expropriation** in the ERA act
 - 3.3 Engagement with DEFF planned to request **quicker environmental approvals** for areas not classified as low and medium risk
 - 3.4 Engagements with DTIC on **exemptions from localisation** requirements, in particular transformers and possibly fabricated structural steel
 - 3.5 Pre-qualification of **addition transformer manufacturers undertaken by** Eskom [8 (previous) 14 (now) 21 planned]
 - 3.6 Decision taken to augment project development capability with **OE**; specification under development

What ACTIONS has Transmission taken?



- 3. Some key items being driven (contd)
 - 3.7 Looking at contracting options such as **EPC**; 13 projects identified
 - 3.8 Availability of **enabling contracts** (professional services, commodities) tightly managed
 - 3.9 Strict management of **schedules** and **reporting visibility** tool under development





END